

3
a
THE STEM BEING LAMINATED to form a stronger construction than the jointed one, originally drawn by the designer.

b
STEAM BENT AMERICAN WHITE OAK timbers riveted in place, Columbian Pine stringers and beam shelf are in position. One bulkhead is in position. These bulkheads will form stiffening to the hull besides dividing accommodation. Oak sole bearers are in position. Laminated oak floors are bolted to the keel and through-riveted to the planking providing great strength and reliability. (Galvanised steel floors are sometimes used and are a major source of trouble, especially with a mix of metals). .

